GOUR MAHAVIDYALAYA

ACCREDITED BY NAAC (2nd Cycle) B+

Dr. Ashim Kumar Sarkar, M.Phil, Ph.D Principal principalgourcollege@gmail.com



P.O.: Mangalbari, Dist.: Malda. Pin: 732142 (W.B.) Phone: 03512-260547; Fax: 03512-260547

E-mail: gour_maha@yahoo.co.in Website: www.gourmaha.ac.in

Memo No. 653 /GM/2024

Date: 02/09/2024

TENDER NOTICE

For and on behalf of Gour Mahavidyalaya invites sealed tender Percentage Rate basis from Experienced Contractors /Agencies having valid GST numbers and registered contractors of PWD.

Last date & time of receipt of tenders

: 18-09-2024 at 4.00 P.M

Date & time of opening of tender

: 19/09/2024 at 2.00 P.M

As per attached

Schedule of rates (BOQ)

Sr.	Name of Work	Estimated Cost	Tender cost	Time Limit
	Re –constructions of Z-AI allay Sheet of staircase of canteen of Gour Mahavidyalaya, Malda.	₹ 36092.00	₹ 300.00	20 days.

I we agree to execute the above mentioned work @ at par/..... % above/..... below

Over the estimated amount to the price schedule of rates (BOQ)

- 1. The Tender cost should be in the form of demand draft from any one nationalized banks payable at Principal Gour Mahavidyalaya.
- 2. Bidders should inspect the work station before filling Tender.
- 3. The under signed reserves all the rights to cancel any or all quotation without assigning any reason thereof.
- 4. The contractor should possess GST registration certificate and should enclose a copy of the same the tender.
- 5. The work should be completed within 20 days of the issue of the work order
- 6. The tenders dully filled has to be placed in the tender box kept in the main gate at office, Gour Mahavidyalaya.
- 7. Final payment will be made only after the satisfactory completion of the work.

Copy to:

- 1. Notice Board of the College
- 2. S. D. O. Sadar /Informatics officer.
- 3. College website. gourmaha.ac.in
- 4. Office file.

Dr. Ashim Kumar Sarkar (Principal)

Gour Mahavidyalaya,

Mangalbari, Malda

Principal ¬¬
GOUR MAHAVIDYALAYA
Mangalbari, Malda.

Estimate for Re-construction of Roof by Z-AI- allay sheet of staircase of canteen of Gour Mahavidyalaya, Mangalbari, Malda

PWD (WB) Building Schedule 2017 & Corrizendum

1) Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof (P.W.D schedule page No. 10 & item No.1

Drainwall

Parapet

mx

5

0.300 x

0.250 m

 0.750 m^3

Total = 0.750 m³

@ Rs. 497.00

372.75

2 Supplying, fitting & fixing Zn-Alalloy (55%Al&45%Zn) coating of 150 grams per sq. metre (followed by colour coated on both side) steel sheet work having minimum yield strength of 550 Mpa of trapizoidal profile of approved make (excluding the supporting framework) fitted and fixed with 55mm & 25mm self tapping screw,EPDM Washer1 6mm dia & 3mmth.washe retc. complete with150mm end lap and one corrugation minimum side lap.(Payment to be made on area of finished work) [P.W.D Schedule page no.82, item no.14). (i) In Roof:-

a) With 0.5 mm thick sheet

5.6 m x

m x

19.600 m² Total = 19.600 m²

@ Rs. 896.00 per m² = Rs.

17561.60

3 Brick work with 1st class bricks in cement mortar (1:6)(b) In superstructure, ground floor . [P.W.D Schedule page no. 15 , item no.-8]

1st floor parapet

X

5.600 mx 3.000 mx 0.450 mx 0.450 mx

0.250 0.250

1.260 m³

 0.338 m^3 1.598 m

per m3

= Rs.

8317.99

3157.99

@ Rs. 5,206.88 3 Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (ii) With 1:6 cement mortar. (b) 15 mm thick plaster [P.W.D Schedule page no.189, item no.-1(ii)c)]

parapet Boundrywall 2.000 x 1.000 x

5.600 mx 3.000 mx

1.550 1.550 17.360 m²

4.650 m²

22.010 m @ Rs. 143.48 per m

Total for Work

Add @18.00 % G.S.T.

m

= Rs. = Rs.

29410.34 = Rs. 5293.86

Add @1.00 % Cess

Total = = Rs.

34704.20 = Rs. 347.04 Total = Rs. 35051.24

Add contingency within 3.0%

Say = Rs. = Rs.

35051.00 1041.13 Total = Rs. 36092.13

Say = Rs. 36092.00

Rupees (Thirty six thousand ninety two) only

SAE (W.C) Old Malda Municipality

> Principal -GOUR MAHAVIDYALAYA Mangalbari, Malda.